

BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineer

Yelahanka Division

B.B.M.P. Bengaluru - 64

APPROVED SCHEDULE -'B'

Name of Work:- Asphaltting to roads at Kaveri layout and surrounding areas in ward no -03 Yelahanka
Satellite Town sub Division

Sl	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
1	Removing & Refixing stone slabs of drains and pointing in C.M	sqm	982.80	111.30	One Hundred Eleven Rupees and Thirty Paise
2	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete -do- 7.5 cms thick	sqm	1026.00	742.00	Seven Hundred Forty Two Rupees and No Paise
3	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete. (Data Rate)	sqm	378.00	2337.00	Two Thousand Three Hundred Thirty Seven Rupees and No Paise
4	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH chapter 3. P No. 143/ Item No. 19.1/ PWD SR 2018-19	cum	2685.00	137.80	One Hundred Thirty Seven Rupees and Eighty Paise
5	KSRRB 300-50. Scarifying bituminous course 50mm to 75mm thick along with premix carpet / surface dressing by road roller attached with scarifier without disturbing the base and stacking the debris including cost of all labour charges, HOM of machineries complete as per specifications. MORTH / Chapter 3	sqm	2327.50	40.38	Forty Rupees and Thirty Eight Paise

EXECUTIVE ENGINEER
KRIDL BBMP DIV
BENGALURU-560 011

Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
			Rate	Rate in Words
6 KSRRB M300-59.2: loosening, leveling and compacting original ground supporting embankment to facilitate placement of first layer of embankment, scarified to a depth of 150mm, mixed with water at OMC and then compacted by rolling so as to achieve minimum dry density as given in table 300-2 for embankment construction, complete as per specifications, case-II: compacting original ground supporting embankment, (which includes watering charges & compaction by vibratory roller) MORTH specification No. 3.5.3.4	sqm	3668.75	25.34	Twenty Five Rupees and Thirty Four Paise
7 Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications Clause 401 of MORTH V Revision	cum	117.19	1994.92	One Thousand Nine Hundred Ninety Four Rupees and Ninety Two Paise
8 KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications	cum	2458.41	2001.28	Two Thousand One Rupees and Twenty Eight Paise
9 KSRRB M500-6. Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications Clause 502 of MORTH V revision	sqm	9948.75	36.04	Thirty Six Rupees and Four Paise

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
			Rate	Rate in Words
10 KSRRB 500-11. Providing and laying bituminous macadam on Prepared Surface with crushed Coarse aggregates as per Design mix formulae for base/binding course including loading of aggregates with F.E loader, Hot mixing of Stone aggregates and bitumen in Hot mix plant, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve desired density, but excluding cost of primer/Tack coat including lead, lift and cost of all materials, labour HOM of machinaries complete as per Specifications. MORTH Ch 5. using 40/60 TPH capacity HMP with Mechanical paver Gr-II (50mm - 75mm) with 3.4% VG-30 bitumen	cum	458.38	6172.38	Six Thousand One Hundred Seventy Two Rupees and Thirty Eight Paise
11 KSRRB M500-2: Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and compressed air to receive bituminous treatment including cost of all materials, labours, HOM complete as per specification	sqm	10554.25	5.30	Five Rupees and Thirty Paise
12 KSRRB M500-10. Tack Coat - Providing and applying tack coat using 80/100 grade bitumen (VG 10) in boiler fitted with spray set distributor at the rate of 0.20 kg per sqm on the existing prepared bituminous surface cleaned with mechanical broom. complete as per specifications. MORTH Specification No. 503	sqm	15779.50	12.72	Twelve Rupees and Seventy Two Paise

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010



Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
			Rate	Rate in Words
13 KSRRB M500-19: providing and laying bituminous concrete 40mm thick with 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 5.4 to 5.6% of mix and filler, transporting the hot mix to work site, laying with hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desire compaction as per MORTH specification clause No. 500.9 complete In all respects as per specifications. MORTH specification 30-45mm compacted thickness (GradingII) With 6% bitumen 80/100, No. 161/	cum	632.18	8980.32	Eight Thousand Nine Hundred Eighty Rupees and Thirty Two Paise
14 KSRRB M800-13. Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803	sqm	536.60	454.74	Four Hundred Fifty Four Rupees and Seventy Four Paise
15 KSRRB 300-26.2 For Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means including loading and unloading. From 0.00 to 2.00 Km	cum	2685.00	87.55	Eighty Seven Rupees and Fifty Five Paise

Signature of the contractor
EXECUTIVE ENGINEER
KRIDL BBMP DIVISION
BENGALURU-560 010

Executive Engineer
 Yelahanka Division
 BBMP, Bangalore -64